

Holland ILS Slider System

Cast Load Cell Weighing System (Tractor Only)



The Holland ILS Cast Load Cell is ideal for ease of installation with no welding required. Simply remove the existing brackets and replace with the ILS Load Cell. Great Performance without increasing the Fifth Wheel height.

Key Features:

Reduce installation time by 6-8 hours vs installation time for fixed 5th wheel load cell.

Easy to install. Bolts on and off, no welding required.

Easily moved from truck to truck.

Replaces the existing Holland ILS

Includes a urethane 5th wheel bushing for longevity.

ACCURACY: Typical system error less than .5% Full Scale.



Hutch Cener Hanger System - 9100500

Applications:

- Refuse
- Forestry
- Aggregate
- Dump truck & trailer
- Agriculture

5920 South 194th Street | Kent, WA 98032 | USA
Sales Support: 800-638-5111
Technical Support: 626-202-5047
E-mail: Obw.usa@vpgsensors.com

sionboard.com

SI
ON-BOARD
WEIGHING
A VPG Brand